

- B. Plans (Sewer Main Extension): See *Subsection 11-04*.
- C. Permits: As provided by [District Code §5.04.060](#), Central San permits are effective for a period of 6 months from the date it is issued, unless stated otherwise on the permit. Central San may specify the effective period for any other permit issued by Central San. The expiration date of a permit will be shown on the permit. Central San permits may be renewed in writing, upon submission of a written request and payment of any applicable fees and charges, for up to 2 additional 6-month terms.

### 3-03 Unpermitted Work

Performance of sewer/recycled water work without a permit is a violation of District Code. Central San may employ any enforcement mechanism set forth in [District Code §5.10.020](#) or as otherwise provided by District Code or law against those persons responsible for the unpermitted sewer or recycled water work. The person committing the violation may be subject to a fine or imprisonment as set forth in [District Code §1.08.060](#).

Unpermitted work shall be subject to an administrative fee in addition to all other applicable fees and charges. At the sole discretion of the Inspector, the Contractor or Property Owner may be required to uncover work for inspection and/or conduct CCTV inspection of the work to demonstrate that it meets the requirements of these Specifications. Where work is found to be out of compliance with the requirements of these Specifications, the Contractor or Property Owner shall correct all deficiencies, or shall remove the nonconforming work and replace it with work that complies in all respects with the requirements.

### 3-04 Emergency Work

- A. When a Contractor is contacted by one of its customers for immediate response to repair a sewer/recycled water service line at any time outside of Central San regular inspection hours (see below), the work may be done as an “emergency” response only to the extent required to restore sewer/recycled water service and shall comply with the following:
  1. The Contractor may proceed with emergency work only after leaving a message stating the location and scope of the work required on Central San’s Inspection voicemail.
  2. Excavations for repair work shall not be backfilled until favorable Central San inspection is received; however, excavations shall be properly protected with 4’ x 8’ sheets of 1-1/8” thick plywood in non-traffic areas or with trench plates in traffic areas, to ensure public safety whenever work is not in progress.
  3. The Contractor shall apply for a Central San permit for the work at 8 a.m. on the next Central San business day following any emergency response and shall obtain the permit prior to requesting inspection of the work.